

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION 1</u>			
	<u>BILL NO. 1</u>			
	<u>PRELIMINARIES</u>			
	<u>BUILDING AGREEMENT AND PRELIMINARIES</u>			
	<p>The JBCC Series 2000 Edition 4.1 Code 2101 March 2005 2005 edition prepared by the Joint Building Contracts Committee, shall be the agreement, amended as hereinafter described</p> <p>The Preliminaries for use with the JBCC Series 2000 Principal Building Agreement (May 2005 edition) prepared by the Joint Building Contracts Committee, shall be deemed to be incorporated in these bills of quantities</p> <p>Contractors are referred to the above-mentioned documents for the full intent and meaning of each clause thereof</p> <p>These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the above-mentioned documents</p> <p>Where any item is not relevant to this specific contract such item is marked N/A, signifying "not applicable"</p> <p>Notwithstanding anything to the contrary contained in any of the contract documents including the Principal Building Agreement and the Preliminaries, the provision of the "Preliminaries" as hereinafter set forth shall prevail and shall take precedence</p>			
	Carried Forward		R	
	Section No. 1 Bill No. 1 Preliminaries			

	<p style="text-align: right;">Brought Forward</p> <p><u>PREAMBLES FOR TRADES</u></p> <p>The Model Preambles for Trades (1999 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claim arising from brevity of description of items fully described in the said Model Preambles for Trades will be entertained</p> <p>Supplementary preambles to the Model Preambles covering clauses of a general nature, clauses pertaining to specific materials and amendments to clauses in the Model Preambles are incorporated in these bills of quantities to satisfy the requirements of this project</p> <p>The contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the Model Preambles and in any supplementary preambles</p> <p><u>GENERAL</u></p> <p>If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries each item priced is to be allocated to one or more of the three categories "F", "T" or "V" as the case may be below such item, where "F" denotes a fixed amount (amount not to be varied), "T" denotes an amount variable in proportion to time and "V" denotes an amount variable in proportion to value</p> <p><u>SECTION A - PRINCIPAL BUILDING AGREEMENT</u></p> <p><u>Definitions (A1)</u></p> <p>1 Definitions and interpretation (clause 1)</p> <p>F:..... V:..... T:.....</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 1 Bill No. 1 Preliminaries</p>		<p style="text-align: right;">R</p>	
--	--	--	-------------------------------------	--

Brought Forward		R
<u>Objective and Preparation (A2 to A14)</u>		
2	Offer acceptance and performance (clause 2)	
	F:..... V:..... T:.....	Item
3	Documents (clause 3)	
	F:..... V:..... T:.....	Item
4	Design responsibility (clause 4)	
	F:..... V:..... T:.....	Item
5	Employer's agents (clause 5)	
	F:..... V:..... T:.....	Item
	<p>The principal agent shall:</p> <ul style="list-style-type: none"> - monitor and control progress and scheduling - monitor all contract conditions, and - coordinate the efforts of the employer's agents, the contractor and subcontractors <p>The powers conferred on the principal agent in terms of this clause and/or the exercising of these powers shall not be construed as removing or diminishing any of the obligations of the Contractor in terms of the Principal Building Agreement, whether financial, contractual or otherwise, nor shall the exercising of these powers create any privity of contract as between the Employer or his agents on the one part and the Contractor or subcontractors or suppliers on the other part</p>	
Carried Forward		R
Section No. 1 Bill No. 1 Preliminaries		

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward				R
	The principal agent reserves the right to attend and participate in all contractor/subcontractor's meetings, to invite other employer's agents to attend such meetings at his discretion and to converse and chair any such meetings if the contractor is derelict in his duty in arranging such meetings to the degree of frequency and comprehensiveness dictated in the opinion of the project manager by the circumstances and exigencies of the construction process			
6	Site representative (clause 6)			
	F:..... V:..... T:.....	Item		
7	Compliance with regulations (clause 7)			
	F:..... V:..... T:.....	Item		
8	Works risk (clause 8)			
	F:..... V:..... T:.....	Item		
9	Indemnities (clause 9)			
	F:..... V:..... T:.....	Item		
10	Works insurances (clause 10)			
	F:..... V:..... T:.....	Item		
11	Liability insurances (clause 11)			
	F:..... V:..... T:.....	Item		
Carried Forward				R
Section No. 1 Bill No. 1 Preliminaries				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
12	Effecting insurance (clause 12)		
	F:..... V:..... T:.....	Item	
13	NO CLAUSE	N/A	
14	Security (clause 14)		
	F:..... V:..... T:.....	Item	
<u>Execution (A15-A23)</u>			
15	Preparation for and execution of the works (clause 15)		
	F:..... V:..... T:.....	Item	
16	Access to the works (clause 16)		
	F:..... V:..... T:.....	Item	
17	Contract instructions (clause 17)		
	F:..... V:..... T:.....	Item	
18	Setting out of the works (clause 18)		
	F:..... V:..... T:.....	Item	
<p>The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc exist in order that the necessary arrangements may be made for the rectification of any such encroachments</p>			
Carried Forward			R
Section No. 1 Bill No. 1 Preliminaries			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R
19	<p>Assignment (clause 19)</p> <p>F:..... V:..... T:.....</p> <p>The contractor shall not cede his rights or delegate his obligations in terms of this agreement unless specifically called for by the employer</p>	Item		
20	<p>Nominated subcontractors (clause 20)</p> <p>F:..... V:..... T:.....</p>	Item		
21	<p>Selected subcontractors (clause 21)</p> <p>F:..... V:..... T:.....</p> <p>Written proof is required from subcontract tenderers at tendering that they can meet the JBCC Selected Subcontract Agreement or other tender agreements and provide security in terms of the agreement. If the above is not provided the tender may not be accepted</p> <p>All amounts allowed under Provisional Amounts are intended to be awarded to Selected Subcontractors</p>	Item		
22	<p>Employer's Direct Contractors (clause 22)</p> <p>F:..... V:..... T:.....</p>	Item		
23	<p>Contractor's Domestic Sub-Contractors (Clause 23)</p> <p>F:..... V:..... T:.....</p> <p><u>Completion (A24-A30)</u></p>	Item		
24	<p>Practical completion (clause 24)</p> <p>F:..... V:..... T:.....</p>	Item		
	Carried Forward			R
	<p>Section No. 1 Bill No. 1 Preliminaries</p>			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R	
25	Works completion (clause 25)				
	F:..... V:..... T:.....	Item			
26	Final completion (clause 26)				
	F:..... V:..... T:.....	Item			
27	Latent defects liability period (clause 27)				
	F:..... V:..... T:.....	Item			
28	Sectional completion (clause 28)				
	F:..... V:..... T:.....	Item			
29	Revision of date of practical completion (clause 29)				
	F:..... V:..... T:.....	Item			
	The removal and replacement of materials and/or workmanship that do not conform to specification or drawings shall not constitute grounds for an extension of the construction period nor for an adjustment to the contract sum (clause 29.3)				
30	Penalty for non-completion (clause 30)				
	F:..... V:..... T:.....	Item			
	<u>Payment (A31 - A35)</u>				
31	Interim payment to the contractor (clause 31)				
	F:..... V:..... T:.....	Item			
	Carried Forward			R	
	Section No. 1 Bill No. 1 Preliminaries				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward				R
32	Adjustment to the contract value (clause 32)			
	F:..... V:..... T:.....	Item		
	Where prices are submitted by the contractor or nominated/selected subcontractors during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing			
33	Recovery of expense and loss (clause 33)			
	F:..... V:..... T:.....	Item		
34	Final account and final payment (clause 34)			
	F:..... V:..... T:.....	Item		
	The employer shall not pay any interest on amounts payable to the contractor for one hundred and forty two (142) days after the date of issue of the certificate of practical completion			
	The employer shall, however, pay interest to the contractor at the rate stipulated in clause 34.11 on any amounts payable to the contractor more than one hundred and forty two (142) days after the date of issue of the certificate of practical completion but only for such period as the settlement of the final account is delayed by the non-performance of the principal agent or the employer or his agents. In evaluating non-performance for purposes of this clause a reasonable time shall be allowed to the employer or his agents to respond to any matter brought to his/their attention and which may affect the settlement of the final account			
Carried Forward				R
Section No. 1 Bill No. 1 Preliminaries				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward		R	
35	Payment to other parties (clause 35) F:..... V:..... T:.....	Item		
	<u>Cancellation (A36-A39)</u>			
36	Cancellation by employer - contractor's default (clause 36) F:..... V:..... T:.....	Item		
37	Cancellation by employer - loss and damage (clause 37) F:..... V:..... T:.....	Item		
38	Cancellation by contractor - employer's default (clause 38) F:..... V:..... T:.....	Item		
39	Cancellation - cessation of the works (clause 39) F:..... V:..... T:.....	Item		
	<u>Dispute (A40)</u>			
40	Dispute Settlement (clause 40) F:..... V:..... T:.....	Item		
	<u>Substitute Provisions (A41)</u>			
41	State clauses (Clause 41) F:..... V:..... T:.....	Item		
	Carried Forward		R	
	Section No. 1 Bill No. 1 Preliminaries			

	Brought Forward		R
	Information necessary for the completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder		
	<u>THE SCHEDULE</u>		
	Information necessary for completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder		
42	Pre-tender information (clause 42)		
	F:..... V:..... T:.....	Item	
	<u>42.1 CONTRACTING AND OTHER PARTIES</u>		
	42.1.1 Employer: As per infomation on the tender data		
	42.1.2 Principal Agent: As per the infomation on the Tender data		
	42.1.3 Architect:		
	42.1.4 Quantity Surveyor:		
	Structural :		
	42.1.5 Civil:		
	42.1.6 Electrical Engineer:		
	42.1.6 Mechanical Engineer:		
	Carried Forward		R
	Section No. 1 Bill No. 1 Preliminaries		

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>42.2 CONTRACT DETAILS</u>			
42.2.1 Works Description: Construction of sanitation facilities			
42.2.2 Site Description: as per the information on the tender data			
42.2.3 Work or installations by direct contractors: N/A			
42.2.4 This agreement is for a government contract where there are specific options that are applicable to a State organ only Yes			
42.2.5 Date on which possession of the site is intended to be given: UNKNOWN			
42.2.6 Period for the commencement of the works after the contractor takes possession			
42.2.7 For the works as a whole . Intended date of practical completion and the penalty per calendar day 3 months after contractual commencement date <i>Date</i> <i>Penalty Amount</i> <i>The penalty per calendar day shall be 0.05% of the tender amount (inclusive of value added tax)</i>			
Carried Forward			R
Section No. 1 Bill No. 1 Preliminaries			

Brought Forward	R
42.2.8 For the works in sections : Intended date of practical completion and the penalty per calender day	
Section 1	
.N/A..... Date	
R.N/A..... Penalty Amount	
42.2.9 The law applicable to this agreement shall be that of	
<i>South Africa (country)</i>	
<u>42.3 INSURANCES</u>	
42.3.1 Contract works insurance to be effected by:	
<i>Contractor:</i>	
<i>For the Sum of R Contract Amount + 20.00 %</i>	
<i>With a deductible of - to be determined by the contractor</i>	
42.3.2 Supplementary insurance is required	
<i>No</i>	
42.3.3 Public liability insurance to be effected by:	
<i>Contractor:</i>	
<i>For the Sum of R 2 500 000-00</i>	
<i>With a deductible of - to be determined by the contractor</i>	
<u>42.4 DOCUMENTS</u>	
42.4.1 Waivers of contractors lien or right of continuing possession is required	
<i>Yes</i>	
42.4.2 Number of construction document copies to be supplied to the contractor free of charge:	
3 Number of	
Carried Forward	R
Section No. 1	
Bill No. 1	
Preliminaries	

	Brought Forward			R
42.4.3	Bills of Quantities/Lump sum document schedule of rates drawn up in accordance with: “Standard System of Measuring Builders’ Work”			
42.4.4	On acceptance of the tender the bills of quantities/lump sum document is to be submitted within working days <i>The priced bills of quantities must be handed in with the tender</i>			
42.4.5	JBCC Engineering General Conditions are to be included in the contract documents : <div style="text-align: right;">No</div>			
42.4.6	The contract value is to be adjusted using escalation adjustment indices <div style="text-align: right;">NO</div>			
42.4.7	Details of changes made to the provision of JBCC standard documentation:			
	<u>SECTION B: PRELIMINARIES</u>			
	<u>Definitions and interpretation (B1)</u>			
43	Definition and interpretation (B1.1 - B1.4.6) F:..... V:..... T:.....	Item		
	<u>Documents (B2)</u>			
44	Checking of documents (B2.1) F:..... V:..... T:.....	Item		
45	Provisional bills of quantities (B2.2) F:..... V:..... T:.....	N/A		
	Carried Forward			R
	Section No. 1 Bill No. 1 Preliminaries			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward		R
46	Availability of construction documentation (B2.3) F:..... V:..... T:.....	Item
47	Interests of agents (B2.4) F:..... V:..... T:.....	Item
48	Priced documents (B2.5) F:..... V:..... T:.....	Item
49	Tender submission (B2.6) F:..... V:..... T:.....	Item
50	Defined works area (B3.1) F:..... V:..... T:.....	Item
<u>The site (B3)</u>		
51	Geotechnical investigation (B3.2) F:..... V:..... T:.....	Item
52	Inspection of the site (B3.3) F:..... V:..... T:.....	Item
	Existing premises occupied (B3.4) F:..... V:..... T:.....	
Carried Forward		R
Section No. 1 Bill No. 1 Preliminaries		

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward		R
Previous work - dimensional accuracy (B3.5)		
F:..... V:..... T:.....		
Previous work - defects (B3.6)		
F:..... V:..... T:.....		
53 Services - known (B3.7)		
F:..... V:..... T:.....	Item	
54 Services - unknown (B3.8)		
F:..... V:..... T:.....	Item	
55 Protection of trees etc (B3.9)		
F:..... V:..... T:.....	Item	
56 Articles of value (B3.10)		
F:..... V:..... T:.....	Item	
<u>Management of contract (B4)</u>		
57 Inspection of adjoining properties etc (B3.11)		
F:..... V:..... T:.....	Item	
58 Management of the works (B4.1)		
F:..... V:..... T:.....	Item	
Carried Forward		R
Section No. 1 Bill No. 1 Preliminaries		

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward	R
59	Programme for the works (B4.2) F:..... V:..... T:.....	Item
60	Progress meetings (B4.3) F:..... V:..... T:.....	Item
61	Technical meetings (B4.4) F:..... V:..... T:.....	Item
62	Labour and Plant records (B4.5) F:..... V:..... T:.....	Item
	Samples, Shop Drawings and Manufacturer's Instructions (B5)	
63	Samples of materials (B5.1) F:..... V:..... T:.....	Item
64	Workmanship samples (B5.2) F:..... V:..... T:.....	Item
65	Shop drawings (B5.3) F:..... V:..... T:.....	Item
66	Compliance with Manufacturer's Instructions (B5.4) F:..... V:..... T:.....	Item
	Carried Forward	R
Section No. 1 Bill No. 1 Preliminaries		

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Temporary works and plant (B6)</u>			
67	Deposits and fees (B6.1)		
	F:..... V:..... T:.....	Item	
68	Enclosure of the works (B6.2)		
	F:..... V:..... T:.....	Item	
69	Advertising (B6.3)		
	F:..... V:..... T:.....	Item	
70	Plant, equipment, sheds and offices (B6.4)		
	F:..... V:..... T:.....	Item	
71	Main notice board (B6.5)		
	F:..... V:..... T:.....	Item	
72	Subcontractors' notice board (B6.6)		
	F:..... V:..... T:.....	N/A	
<u>Temporary services (B7)</u>			
73	Location (B7.1)		
	F:..... V:..... T:.....	Item	
Carried Forward			R
Section No. 1 Bill No. 1 Preliminaries			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
74	Water (B7.2)		
	Option [A] shall apply		
	F:..... V:.....	Item	
	T:.....		
75	Electricity (B7.3)		
	Option [A] shall apply		
	F:..... V:.....	Item	
	T:.....		
76	Telecommunication facilities (B7.4)		
	F:..... V:.....	Item	
	T:.....		
77	Ablution facilities (B7.5)		
	Option [A] shall apply		
	F:..... V:.....	Item	
	T:.....		
	<u>Prime cost amounts (B8)</u>		
78	Responsibility for prime cost amounts (B8.1)		
	F:..... V:.....	Item	
	T:.....		
	<u>Attendance on N/S Subcontractors (B9)</u>		
79	General attendance (B9.1)		
	F:..... V:.....	Item	
	T:.....		
80	Special attendance (B9.2)		
	F:..... V:.....	Item	
	T:.....		
Carried Forward			R
Section No. 1			
Bill No. 1			
Preliminaries			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward		R
81	Commissioning - Fuel, water and power (B9.3)	
	F:..... V:..... T:.....	Item
	<u>Financial aspects (B10)</u>	
	Statutory taxes, duties and levies (B10.1)	
	F:..... V:..... T:.....	Item
82	Payment of preliminaries (B10.2)	
	Option [B] shall apply	
	F:..... V:..... T:.....	Item
83	Adjustment of preliminaries (B10.3)	
	Option [A] shall apply	
	F:..... V:..... T:.....	Item
84	Payment certificate cash flow (B10.4)	
	F:..... V:..... T:.....	Item
	<u>General (B11)</u>	
85	Protection of works (B11.1)	
	F:..... V:..... T:.....	Item
86	Protection/isolation of existing/sectionally occupied works (B11.2)	
	F:..... V:..... T:.....	Item
Carried Forward		R
Section No. 1 Bill No. 1 Preliminaries		

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
87	Security of the Works (B11.3)		
	F:..... V:..... T:.....	Item	
88	Notice before covering work (B11.4)		
	F:..... V:..... T:.....	Item	
89	Disturbance (B11.5)		
	F:..... V:..... T:.....	Item	
90	Environmental Disturbance (B11.6)		
	F:..... V:..... T:.....	Item	
91	Works cleaning and clearing (B11.7)		
	F:..... V:..... T:.....	Item	
92	Vermin (B11.8)		
	F:..... V:..... T:.....	Item	
93	Overhand work (B11.9)		
	F:..... V:..... T:.....	Item	
94	Instruction manuals and guarantees (B11.10)		
	F:..... V:..... T:.....	Item	
95	As built information (B11.11)		
	F:..... V:..... T:.....	Item	
Carried Forward			R
Section No. 1			
Bill No. 1			
Preliminaries			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

[illegible]

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward				R
12.1.10	Protection of trees (B3.9)			
	All trees should be protected and only on instruction of the Principal Agent may any trees be removed			
12.1.12	Enclosure of the works (B6.2)			
12.1.11 (B3.11)	Inspection of adjoining properties			
12.1.13	Offices (B6.4.3)			
	An office for the clerck of works should be provided			
12.1.14	Main notice board (B6.5)			
		YES		
12.1.15	Subcontractors notice board (B6.6)			
	A notice board is required			
		No		
12.1.16	Water (B7.2)			
	Alternative Selected: A			
12.1.17	Electricity (B7.3)			
	Alternative selected: A			
12.1.18	Telecommunications (B7.4)			
12.1.19	Ablution facilities (B7.5)			
	Alternative selected: A			
12.1.20	Protection of existing/sectionally occupied works (B11.2)			
12.1.21	Special attendance (B9.2)			
	Subcontractor (1) details:			
	N/A			
Carried Forward				R
Section No. 1				
Bill No. 1				
Preliminaries				

	Brought Forward			R
	12.1.22 Protection of the works (B11.1)			
	N/A			
	12.1.23 Disturbance (B11.5)			
	N/A			
	12.1.24 Environmental Disturbance (B11.6)			
	N/A			
	<u>Post tender information (B12.2)</u>			
	12.2.1 Payment of preliminaries Alternative selected: B			
	12.2.2 Adjustment of preliminaries Alternative selected: A			
	12.2.3 Additional agreed preliminaries items N/A			
	<u>SECTION C: SPECIFIC PRELIMINARIES</u>			
	Any special items to meet the particular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included			
98	Site instructions			
	Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor			
	F: V:..... T:.....	Item		
99	Black economic empowerment and training			
	F:..... V:..... T:.....	Item		
	Carried Forward			R
	Section No. 1 Bill No. 1 Preliminaries			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R	
100	<p>Proprietary branded products</p> <p>F:..... V:..... T:.....</p>		Item		
101	<p>Testing of flat roof waterproofing for watertightness</p> <p>Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing</p> <p>F:..... V:..... T:.....</p> <p>The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instructions after consultation with the manufacturer's authorised representative</p>		Item		
102	<p>Contract instructions</p> <p>F:..... V:..... T:.....</p> <p>Contract instructions issued on site are to be recorded in triplicate in a contract instruction book which is to be supplied and maintained on site by the contractor</p>		Item		
103	<p>Labour record</p> <p>F:..... V:..... T:.....</p> <p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and descriptions of tradesmen and labourers employed by him and all subcontractors on the works each day of that week</p>		Item		
	Carried Forward			R	
	<p>Section No. 1 Bill No. 1 Preliminaries</p>				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R	
104	Plant record F:..... V:..... T:..... At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools used on the works each day of that week	Item			
105	Guarantees F:..... V:..... T:..... Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor. The principal agent shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement	Item			
106	Overtime F:..... V:..... T:..... Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer	Item			
	Carried Forward			R	
	Section No. 1 Bill No. 1 Preliminaries				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward		R	
107	Co-operation of contractor for cost management F:..... V:..... T:..... It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors	Item		
108	Occupational Health and Safety Specification F:..... V:..... T:.....	Item		
	<u>SUMMARY OF CATEGORIES</u> Category : Fixed R..... Category : Value R..... Category : Time R.....			
	Carried to Final Summary		R	
	Section No. 1 Bill No. 1 Preliminaries			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION 2</u>			
	<u>BUILDING WORK</u>			
	<u>BILL NO 1</u>			
	<u>ALTERATIONS</u>			
	For preambles see "Construction works: Specifications: General Specification (PW 371-A) Edition 2.0"			

	<u>TEMPORARY BARRIERS, SCREENS, ETC</u>			
	<u>Temporary barriers, screens, etc including removal</u>			
1	Shade netting barrier 2000mm high formed of steel channel section rails, etc	m	350	
	<u>DEMOLITIONS ETC</u>			
	<u>DEMOLITION OF EXISTING TOILET STRUCTURES</u>			
2	Single storey two seater pit latrines with pitched roof approximately combined area of 15m2 on plan and 3m high at eaves comprising concrete surface bed, one brick external walls, one brick and half brick internal walls and corrugated roof covering on prefabricated timber trusses including removal of foundation brickwork, strip footings and aprons including, backfilling, cart away etc.of all rubble and leaving no visible sign of the building (hand over usable items to school	No	2	
	Carried Forward		R	
	Section No. 2 Bill No. 1 ALTERATIONS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward		R
3	Single storey three seater pit latrines with pitched roof approximately combined area of 20m2 on plan and 3m high at eaves comprising concrete surface bed, one brick external walls, one brick and half brick internal walls and corrugated roof covering on prefabricated timber trusses including removal of foundation brickwork, strip footings and aprons including, backfilling, cart away etc.of all rubble and leaving no visible sign of the building (hand over usable items to school)	No 1
Carried Forward to Summary of Section No. 2		R
Section No. 2		
Bill No. 1		
ALTERATIONS		

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No	Quantity	Rate	Amount
<u>SECTION NO.2</u>			
<u>BUILDING WORKS</u>			
<u>BILL NO.2</u>			
<u>EARTHWORKS</u>			
For preambles see "Construction works: Specifications: General Specification (PW 371-A) Edition 2.0"			

<u>SITE CLEARANCE</u>			
<u>Site clearance</u>			
1	Digging up and removing rubbish, debris, vegetation , hedges, shrubs ,bush, etc and tress not exceeding 200mm girth.	m2	567
2	Stripping average 150mm thick layer of top soil and depositing material in prescribed stock piles on site.	m2	567
<u>EXCAVATIONS ETC</u>			
<u>Open face excavation in earth over sloping site</u>			
3	Open face excavation	m3	92
4	To remove sloping banks	m3	150
<u>EXCAVATION OTHER THAN BULK</u>			
<u>Excavation in earth not exceeding 2m deep</u>			
5	Reduced levels under floors	m3	26
6	Trenches	m3	70
7	Pits	m3	185
Carried Forward			R
Section No. 2 Bill No. 2 EARTHWORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R
	<u>Excavation in earth exceeding 2m and not exceeding 4m</u>			
8	Pits	m3	15	
	<u>Extra over excavations other than in earth for excavation in</u>			
9	Soft rock	m3	115	
10	Hard rock	m3	121	
	<u>Risk of collapse of excavations other than bulk</u>			
11	Sides of trench and hole excavations not exceeding 1,5m deep	m2	284	
12	Side of trench and hole excavations exceeding 1,5m deep.	m2	170	
	<u>CARTING AWAY</u>			
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk)</u>			
13	Off site to a dumping site to be found by the contractor	m3	220	
	<u>FILLING, ETC OTHER THAN BULK</u>			
	<u>Filling with material from the excavations compacted to a density of at least 95% Mod.AASHTO maximum density</u>			
14	Backfilling to trenches, holes, etc	m3	40	
	<u>Filling with G7 material in accordance with SABS 1200 DM, material supplied and carted onto site by the Contractor, compacted to a density of at least 95% Mod.AASHTO maximum density</u>			
15	Backfilling to trenches, holes, etc	m3	55	
16	Under floors etc	m3	32	
	<u>Coarse river sand filling supplied by the contractor</u>			
17	Under floors etc	m3	16	
	Carried Forward			R
	Section No. 2			
	Bill No. 2			
	EARTHWORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>KEEPING EXCAVATIONS FREE OF WATER</u>			
18	Keeping excavations free of water all water other than subterranean water	Item	
<u>TESTS</u>			
<u>Prescribed density tests on filling</u>			
19	Modified AASHTO Density test	No	8
<u>Compaction of surfaces</u>			
20	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2	132
<u>SOIL POISONING</u>			
<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control company and guaranteed against termite infestation for ten years</u>			
21	Under floors, etc, including forming and poisoning shallow furrows against foundation walls, etc, filling in furrows and ramming	m2	132
22	To bottoms and sides of trenches, holes, etc	m2	414
Carried Forward to Summary of Section No. 2			R
Section No. 2			
Bill No. 2			
EARTHWORKS			

Item No	Quantity	Rate	Amount
<u>SECTION NO.2</u>			
<u>BUILDING WORKS</u>			
<u>BILL NO.3</u>			
<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>			
For preambles see "Construction works: Specifications: General Specification (PW 371-A) Edition 2.0"			

<u>UNREINFORCED CONCRETE</u>			
<u>15Mpa/19mm Concrete</u>			
1	Filling of cavity wall	m3	4
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
<u>25MPa/19mm Concrete</u>			
2	Raft foundation	m3	23
<u>REINFORCED CONCRETE</u>			
<u>25MPa/19mm Concrete</u>			
3	Surface beds cast in panels on waterproofing	m3	33
4	Slabs including beams and inverted beams. (Pits)	m3	22
<u>FINISHING TOP SURFACE OF CONCRETE</u>			
<u>Finishing top surface of concrete smooth with a steel trowel</u>			
5	Surface beds, slabs, etc	m2	128
<u>TEST BLOCKS</u>			
Carried Forward			R
Section No. 2 Bill No. 3 CONCRETE, FORMWORK AND REINFORCEMENT			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Test blocks</u>			
6	Making and testing set of three 150 x 150 x 150mm concrete strength test cubes	Sets	15.0
<u>CONCRETE SUNDRIES</u>			
7	45 x 12mm Half round grooves in top.	m	172
<u>ROUGH FORMWORK (DEGREE OF ACCURACY II)</u>			
<u>Rough Formwork to sides</u>			
8	Edges, risers , ends and reveals not exceeding 200mm high or wide	m	172
<u>Permanent formwork to soffits</u>			
9	Soffit to slab	m2	132
<u>Rough formwork to form</u>			
10	250mm Diameter opening through 125mm slab	No	18
11	150mm Diameter opening through 125mm slab	No	18
<u>MOVEMENT JOINTS, ETC</u>			
<u>3 ply Malthoid in slip joints between horizontal concrete and brick surfaces including cement mortar bed</u>			
12	Not exceeding 300mm wide.	m	42
<u>REINFORCEMENT</u>			
<u>High tensile steel reinforcement to structural concrete work</u>			
13	16mm Diameter bars	t	1.48
14	12mm Diameter bars	t	2.30
Carried Forward			R
Section No. 2 Bill No. 3 CONCRETE, FORMWORK AND REINFORCEMENT			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

[illegible]

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

[illegible]

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward				R
<u>Brickwork of NFX bricks (14MPa nominal compressive strength) in class I mortar</u>				
1	Half brick walls	m2	75	
2	Half brick linings to concrete	m2	34	
3	One brick walls	m2	266	
4	One brick walls of two half brick skins with inner skin bagged and sealed	m2	158	
<u>BRICKWORK IN SUPERSTRUCTURE</u>				
<u>Brickwork of NFP bricks in class II mortar</u>				
5	Half brick walls	m2	84	
6	One brick walls	m2	448	
7	Half brick wall in beam filling	m2	34	
<u>BRICKWORK SUNDRIES</u>				
<u>Turning pieces</u>				
8	115mm Wide turning piece to lintels, etc	m	37	
<u>Brickwork reinforcement</u>				
9	75mm Wide reinforcement built in horizontally	m	988	
10	150mm Wide reinforcement built in horizontally.	m	1 455	
<u>Prestressed fabricated lintels</u>				
11	110 x 75mm Lintels in lengths not exceeding 3m	m	50	
<u>Galvanised hoop iron cramps, ties, etc</u>				
12	30 x 1,6mm Roof tie 1,5m long with one end fixed to timber and other end built into brickwork	No	122	
<u>Air bricks etc</u>				
13	229 x 152mm Clay vermin proof of air brick	No	24	
Carried Forward				R
Section No. 2 Bill No. 5 MASONRY				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>FACE BRICKWORK</u>			
<u>"Corobrik Firelight Satin" face bricks pointed with recessed horizontal and vertical joints</u>			
14	Extra over brickwork for face brickwork	m2	665
15	Extra over brickwork for face brickwork in beamfilling	m2	34
16	Fair raking cutting	m	30
17	Extra over brickwork for brick-on-edge header course coping	m	14
18	Extra over brickwork for brick-on-edge header course lintels one course high, pointed on face and 115mm soffit	m	37
19	Fair cutting and fitting around pipe not exceeding 100mm diameter	No	14
20	Fair cutting and fitting around pipe exceeding 200mm and not exceeding 300mm diameter	No	9
<u>FACE BRICKWORK COPINGS, SILLS, ETC</u>			
<u>"Corobrik Firelight Satin" face bricks pointed with recessed horizontal and vertical joints</u>			
21	200mm Wide sill set sloping and slightly projecting	m	25
<u>FIBRE-CEMENT WINDOW SILLS</u>			
<u>Natural grey window sills in single lengths not exceeding 3.6m, bedded in class I mortar including fixing lugs screwed to underside with self tapping screws</u>			
22	15 x 150mm Wide sills set flat and slightly projecting	m	25
Carried Forward to Summary of Section No. 2			R
Section No. 2			
Bill No. 5			
MASONRY			

[illegible]

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

[illegible]

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION NO.2</u>			
	<u>BUILDING WORKS</u>			
	<u>BILL NO.8</u>			
	<u>CARPENTRY AND JOINERY</u>			
	<u>Trade Preambles:</u> For Trade Preambles refer to 'Specification of Materials and Methods' (PW371) for the full descriptions of material to be used and work to be done in this Bill			
	<u>SUPPLEMENTARY PREAMBLES</u> Proprietary items or materials: Proprietary items or materials where specified are to be of the brand specified -or other approved -by the Principal Agent. -----			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	<u>ROOFS</u>			
	<u>Sawn softwood</u>			
1	38 x 114mm Rafters in lengths exceeding 3.9m and not exceeding 6.6m	m	201	
2	38 x 114mm Wall plates	m	92	
3	50 x 76mm Purlins in lengths exceeding 3.9m and not exceeding 6.6m	m	206	
	<u>DOORS, ETC.</u>			
	<u>Wrought meranti doors hung to steel frames</u>			
4	44mm Framed batten door 813 x 2032mm high braced and ledged timber meranti door (D3) the entire door to be sanded down and apply 1 coat pink wood primer and two full coats velvagro polyurethane velvet enamel fixed to 1100mm high long single action purpose cut timber meranti log/jamb	No	6	
	Carried Forward			
	Section No. 2 Bill No. 8 CARPENTRY AND JOINERY		R	

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Solid core flush doors with concealed hardwood edges and 4mm thick masonite covering on both sides hung to steel frame</u>			
5	40mm Door 813 x 1882mm high	No	19
<u>ROOF SUNDRIES</u>			
6	6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together	No	24
7	Hurricane clips	No	48
8	Two coats creosote on sawn timbers	m2	125
<u>EAVES, VERGES, ETC.</u>			
<u>Medium density plain fibre-cement fascial and barge boards:</u>			
9	12 x 225mm Fascia and barge boards, including galvanised steel H-profile joiners, etc.	m	75
10	85 x 275mm Barge boards fixed to roof timbers including galvanised steel H-profile joiners, etc.	m	70
Carried Forward to Summary of Section No. 2			R
Section No. 2			
Bill No. 8			
CARPENTRY AND JOINERY			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION NO.2</u>			
	<u>BUILDING WORKS</u>			
	<u>BILL NO.9</u>			
	<u>IRONMONGERY</u>			
	For preambles see "Construction works: Specifications: General Specification (PW 371-A) Edition 2.0"			

	<u>EN-SUITE LOCKS</u>			
	<u>En-suite locks</u>			
1	Pair of 'Union CZ692-24SC' or equal approved radius lever handles on back plate and one 'Union 2201 78PL' or equal approved three lever upright lock set, fixed to steel.	No	6	
2	Indicator lockset	No	19	
	<u>HINGES</u>			
3	1 Pair "Union" or similar approved butt hinges' with stainless steel finish	No	48	
	<u>Keys:</u>			
4	'Union' or equal approved master key.	No	8	
	<u>LETTERS, NAMEPLATES, ETC.</u>			
	<u>Clear Perspex name plate size 150 x 150mm high with Arial font lettering 40mm high cut out blue vinyl backing, twice holed for and including fixing horizontally to timber door with two dome-headed stainless steel selftapping screws:</u>			
5	'BOYS' signplate. plugged	No	1	
6	'GIRLS' signplate, plugged.	No	1	
	Carried Forward			
	Section No. 2 Bill No. 9 IRONMONGERY		R	

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R
7	' GRADE R' signplate, plugged.	No	1	
8	'DISABLED' signplate, plugged.	No	1	
9	'MALE TEACHERS' signplate, plugged.	No	1	
10	'FEMALE TEACHERS' signplate, plugged.	No	1	
<u>BATHROOM FITTINGS</u>				
<u>Chairman industries or similar approved brushed stainless steel grab rails.</u>				
11	32mm Diameter code DL2 side grab rail, plugged.	No	1	
12	32mm Diameter code SR2 rear grab rail around cistern, plugged.	No	1	
<u>Toilet roll holder:</u>				
13	'Halcast steel"134-CP toilet roll holder with spring roller with chrome plated finish, plugged to wall.	No	19	
<u>SUNDRIES</u>				
<u>Sundries:</u>				
14	'Union' CZ8731SC or equal approved buffered door stop, plugged.	No	6	
Carried Forward to Summary of Section No. 2				R
Section No. 2				
Bill No. 9				
IRONMONGERY				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION NO.2</u>			
	<u>BUILDING WORKS</u>			
	<u>BILL NO.10</u>			
	<u>METALWORK</u>			
	For preambles see "Construction works: Specifications: General Specification (PW 371-A) Edition 2.0"			

	<u>Descriptions</u>			
	Descriptions of bolts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete Metalwork described as"holed for bolt(s)" shall be deemed to exclude the bolts unless otherwise described			
	<u>STEEL WINDOWS, DOORS, ETC</u>			
	<u>GALVANISED PRESSED STEEL DOOR FRAMES</u>			
	<u>1.6mm Double rebated frames suitable for one brick walls with two 100mm galvanised loose pin hinges per door leaf</u>			
1	Frame for door 813 x 2032mm high	No	6	
	<u>1.6mm Double rebated frames suitable for half brick walls with two 100mm galvanised loose pin hinges per door leaf</u>			
2	Frame for door 813 x 1882mm high	No	19	
	<u>ALUMINIUM WINDOWS, DOORS, ETC</u>			
	<u>Doors, windows, etc to be manufactured by an approved firm of specialists, to be of the best quality and design truly squared and unless otherwise described, prepared to receive glazing beads from the outside. All opening portions must fit perfectly on all faces and be so hung as to open and close freely without binding at any point.</u>			
	Carried Forward		R	
	Section No. 2 Bill No. 10 METALWORK			

<p style="text-align: center;">Brought Forward</p> <p><u>Wherever possible, all angles and intersections to be welded by electric welding, argon or arc welding. A sample window is to be submitted to the Architect for approval before the work is put in hand.</u></p> <p><u>The frames generally are to be suitable for brickwork, blockwork, or concrete reveals. They are to be fitted with fixing lugs of 2,8mm aluminium 13mm wide x 100mm long welded to framing, one near each corner and intermediately not more than 300mm apart to sides top and bottom. Where concrete reveals, etc the frames are to be countersunk holed for and fitted with the necessary screws at the centres as for the lugs above.</u></p> <p><u>Immediately after the windows, doors, etc, have been delivered on to site, they are to be thoroughly overhauled, and all necessary adjustment or repairs made before they are fixed in position. Where they come into contact with brickwork, blockwork, concrete, steel, etc, the framing is to be treated with bituminous paint in an approved manner. The windows, doors, etc, are to be placed in their positions for building in and adjusted to open and close properly and are to be securely structured to prevent distortion whilst the brickwork and lintels, are being built.</u></p> <p><u>On completion of all other work the windows, doors, are to be adjusted as necessary and rendered in a complete and satisfactory state of repair and in working order.</u></p> <p><u>General. All rates for doors, windows, shop fronts etc, should include for all glazing as specified.</u></p> <p><u>Glazing beads: All door, etc to be fitted with glazing beads, unless otherwise described, mitred at angles and screwed on.</u></p> <p><u>Glass and Glazing: All functional glass must be delivered to site cut to size and ready for installation and must be classified to indicate grade and thickness. Labels must remain on each piece of glass until it is glazed, inspected and officially accepted in writing by the employer, thereafter an insurance letter will follow absolving the contractor of responsibility.</u></p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 2 Bill No. 10 METALWORK</p>		R	

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Powder Coated or similar approved aluminium windows, doors, etc including sub-frames, fixing, silicone sealant all round, ironmongery and glazed with 6mm clear laminated safety glass unless otherwise stated</u>			
3	Window size 600 x 600mm high, (W01)	No	20
4	Window size 900 x 600mm high, (W02)	No	8
<u>WELDED SCREENS, GATES, ETC</u>			
<u>Screens and gates</u>			
5	Galvanised single gate and frame 900 x 2100mm high comprising of 25 x 25 x 2mm hollow section frame and 25 x 25 x 2mm hollow section middle rail filled in with 12 x 12mm square section vertical rails at 75mm centres and fitted with a pair of suitable hinges welded to frame and with locking mechanism all in and including outer frame of 25 x 25 x 2mm hollow section welded frame bolted to brickwork	No	6
Carried Forward to Summary of Section No. 2			R
Section No. 2 Bill No. 10 METALWORK			

Item No		Quantity	Rate	Amount
	<u>SECTION NO.2</u>			
	<u>BUILDING WORKS</u>			
	<u>BILL NO.11</u>			
	<u>PLASTERING</u>			
	For preambles see "Construction works: Specifications: General Specification (PW 371-A) Edition 2.0"			

	<u>SCREEDS</u>			
	<u>Screeds on concrete</u>			
1	5mm Thick x 75mm High coved skirting to brickwork	m	130	
	<u>'Tal Screedmaster' or equal approved self levelling screeds on concrete floors applied as per manufacturers instructions</u>			
2	4mm Thick on floors and landings	m2	142	
	<u>EPOXY</u>			
	<u>Scarify new power floated concrete surfaces as described, sweep clean and prime with epoxy primer, apply 'Flowcrete Flowfresh MF' or equal approved heavy duty chemical resistant antimicrobial treated polyurethane resin floor to a smooth matt colour Ochre finish and seal all in strict accordance with the manufacturers instructions. The work is to be executed by a specialist contractor approved by the manufacturer</u>			
3	4mm Thick on floors and landings	m2	142	
	<u>INTERNAL PLASTER</u>			
	<u>4:1 Cement plaster on brickwork</u>			
4	On walls	m2	701	
5	On narrow widths	m2	46	
	Carried Forward to Summary of Section No. 2		R	
	Section No. 2			
	Bill No. 11			
	PLASTERING			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION NO.2</u>			
	<u>BUILDING WORKS</u>			
	<u>BILL NO.12</u>			
	<u>PLUMBING AND DRAINAGE</u>			
	For preambles see "Construction works: Specifications: General Specification (PW 371-A) Edition 2.0"			

	<u>RAINWATER DISPOSAL</u>			
	<u>0,6mm Seamless coated internally and externally with Colour Tech G4 or similar aluminium rainwater gutters, etc fixed strictly in accordance with manufacturer's instructions</u>			
1	100 x 150mm Eaves gutters in marble white on and including gutter brackets at 1m centres	m	49	
2	Extra over eaves gutter for angle	No	8	
3	Extra over eaves gutter for stopped end	No	4	
4	125 x 75mm Rectangular fluted rainwater downpipes in marble white fixed into the wall with holder bats	m	30	
	<u>SANITARY FITTINGS</u>			
	<u>White glazed vitreous china with Cobra Watertech accessories</u>			
5	White vitreous china rounded lavatory basin with one taphole and complete with chromium plated star pattern basin set, anti-theft plug with spindle and chromium plated bottle trap	No	4	
6	"Atlas Plastics rotomoulded polythene" or similar approved wash hand basin with one taphole and complete with chromium plated star pattern basin set, anti-theft plug with spindle and chromium plated bottle trap	No	12	
	Carried Forward			
	Section No. 2 Bill No. 12 PLUMBING AND DRAINAGE		R	

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R
7	Atlas Plastics rotomoulded polythene or similar approved Junior low level suite VIP 200 pit pedestal-222 with seat and flap colour Granite (Code: 101235), overall size 387 x 518mm high with foot piece and VIP 200 inlet funnel (elsewhere specified) with removable plug.	No	3	
8	"Vaal Pearl Paraplegic Semi Close Couple Suite" product code: 73005C supplied with purpose made C.P side flush lever (right) and purpose made urea seat and cover plate	No	1	
9	"Atlas Plastics rotomoulded polyethylene Viking urinal-508AP colour Granite (Code:101243)" or similar approved with back inlet for concealed flush valve (elsewhere specified), overall size 363 x 320 x 553mm high plugged and screwed to wall with galvanised screws and brackets.	No	3	
	<u>WASTE UNIONS ETC</u>			
	<u>"Cobra Watertech"</u>			
10	15mm, 111CP "Star" pillartap	No	13	
11	32mm "Cobra Ref. 301" slotted basin waste with plug, chain and stay	No	13	
	<u>TRAPS ETC</u>			
	<u>Rubber traps, etc</u>			
12	32 x 40mm 'Flexitap' butyl rubber deep seal 'P' or 'S' trap jointed to waste outlet fitting and to PVC pipe including coupling clamps, etc	No	13	
13	40 x 40mm 'Flexitrap' butyl rubber deep seal 'P' or 'S' trap jointed to waste outlet fitting and to PVC pipe including coupling clamps, etc	No	18	
	<u>SANITARY PLUMBING</u>			
	<u>uPVC pipes and vent pipes</u>			
14	110mm Pipes	m	40	
	Carried Forward			R
	Section No. 2			
	Bill No. 12			
	PLUMBING AND DRAINAGE			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R	
15	50mm Pipes	m	30		
16	50mm Pipes laid in and including trenches not exceeding 1m deep	m	45		
17	150mm Black A/G pipes m 57	m	63		
	<u>Extra over uPVC pipes for fittings</u>				
18	50mm Bend	No	13		
19	50mm Access bend	No	13		
20	50mm Vent valve	No	18		
	<u>Ventilators</u>				
21	240mm Polycarbonate 'Turbo Ventura' ventilator with 150mm diameter throat fixed to top of 150mm vent pipe (vent pipe elsewhere measured)	No	15		
	<u>TESTING</u>				
22	Testing drainage pipe system		Item		
	<u>WATER SUPPLIES</u>				
	<u>Class 0 copper pipes</u>				
23	15mm Pipes	m	45		
24	15mm Pipes chased into brick walls	m	40		
25	22mm Pipes	m	45		
26	22mm Pipes chased into brick walls	m	35		
	<u>Extra over class 0 copper pipes for capillary fittings</u>				
27	15mm Fittings	No	12		
28	22mm Fittings	No	12		
	<u>TESTING</u>				
29	Testing water pipe system		Item		
	Carried Forward to Summary of Section No. 2			R	
	Section No. 2				
	Bill No. 12				
	PLUMBING AND DRAINAGE				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

[illegible]

[illegible]

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
	<u>Prepare and apply on coat zinc chromate to nail heads and H-spline strips, one universal undercoat, stop and apply two finishing coats of eggshell enamel on</u>		
5	On interior cills	m2	8
6	Fascias bargeboards, etc	m2	54
Carried Forward to Summary of Section No. 2			R
Section No. 2			
Bill No. 14			
PAINTWORK			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION 2</u>			
	<u>BILL NO.15</u>			
	<u>WALKWAYS</u>			
	For preambles see "Construction works: Specifications: General Specification (PW 371-A) Edition 2.0"			
	<u>Site clearance</u>			
1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc and trees not exceeding 200mm girth	m2	224	
2	Stripping average 150mm thick layer of top soil and depositing material in prescribed stock piles on site	m2	224	
	<u>EXCAVATION, FILLING, ETC</u>			
	<u>Excavation in earth not exceeding 2m deep</u>			
3	Reduce levels under paved parking and walkways and stockpile	m3	34	
	<u>Extra over all excavations for carting away</u>			
4	Extra over all excavations for carting away surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	30	
	<u>Keeping excavations free of water</u>			
5	Keeping excavations free of water other than subterranean water		Item	
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 98% Mod AASHTO density</u>			
6	Backfilling to platforms	m3	34	
	<u>Coarse river sand filling supplied by the contractor</u>			
7	Under floors etc	m3	67	
	Carried Forward		R	
	Section No. 2			
	Bill No. 15			
	EXTERNAL WORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Compaction of surfaces</u>			
8	Compaction of ground surfaces under pavings etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	224
<u>Prescribed density tests on filling</u>			
9	"Modified AASHTO Density" test	No	4
<u>Weedkillers, insecticides, etc</u>			
10	Weedkiller and soil insecticide mixed in the proportion in strict accordance with the manufacturers instructions applied to earth surfaces under paving	m2	224
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
<u>25MPa/19mm Concrete</u>			
11	Surface bed cast in panels and edge beams	m3	57
<u>CONCRETE SUNDRIES</u>			
<u>Smooth formwork to sides</u>			
12	Edges not exceeding 300mm high	m	40
<u>TEST BLOCKS</u>			
13	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	15
<u>REINFORCEMENT (PROVISIONAL)</u>			
<u>Fabric reinforcement</u>			
14	Ref 193 fabric reinforcement in concrete surface beds, etc	m2	224
<u>RAINWATER TANKS AND STANDS</u>			
Carried Forward			R
Section No. 2 Bill No. 15 EXTERNAL WORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Excavation in earth not exceeding 2m deep</u>			
15	Trenches:	m3	15
<u>Extra over trench and hole excavations in earth for excavation in :</u>			
16	Soft rock	m3	8
17	Hard rock	m3	7
<u>Extra over all excavations for carting away:</u>			
18	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	16
<u>Risk of collapse of excavations:.</u>			
19	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	52
<u>Keeping excavations free of water:</u>			
20	Keeping excavations free of water.		Item
<u>Earth filling supplied by the contractor compacted to 95% Mod ASSHTO density</u>			
21	Backfilling to trenches, holes, etc.:	m3	8
22	Under floors, steps, pavings, etc	m3	22
Carried Forward			R
Section No. 2 Bill No. 15 EXTERNAL WORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Compaction of surfaces:</u>			
23	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density.	m2	24
<u>25 MPa/20mm concrete:</u>			
24	Strip footings	m3	2
25	Surface beds.	m3	4
<u>Sundries:</u>			
26	Extra for setting in position and casting holding down bolt into concrete base.	No	4
<u>Finishing top surfaces of concrete smooth with a wood float:</u>			
27	Tank slabs, surface beds, etc	m2	24
<u>Rough Formwork to sides:</u>			
28	Edges, risers, ends and reveals not exceeding 300mm high or wide.	m	40
<u>Fabric reinforcement:</u>			
29	REF. 156 fabric reinforcement in concrete surface beds, slabs, etc.	m2	24
Carried Forward			R
Section No. 2 Bill No. 15 EXTERNAL WORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
	<u>Brickwork of NFX bricks (14MPa nominal compressive strength) in Class I mortar:</u>		
30	One brick walls.	m2	40
	<u>Brickwork reinforcement:</u>		
31	150mm Wide reinforcement built in horizontally	m	472
	<u>Galvanised hoop iron cramps, ties, etc.:</u>		
32	30 x 1,6mm Tie secured around tank and 4 times built into concrete (Total for one tank = 12 meters).	No	16
	<u>"Corobrik Firelight Satin" face bricks pointed with recessed horizontal and vertical joints</u>		
33	Extra over brickwork for face brickwork externally	m2	40
	<u>One layer of 250 micron 'USB GREEN' waterproof sheeting sealed at laps with 'Gunplas Pressure Sensitive Tape':.</u>		
34	Under surface beds.	m2	24
	<u>Rainwater tanks:</u>		
35	2500 Litre polyethylene rotomoulded vertical water storage tank complete with lid, fitted with and including 15mm brass bibtap (Type 108LK15) with suitable adaptor and setting in position on concrete tankstand (elsewhere measured) and tying down with 4mm diameter galvanised wire wrapped twice around centre of tank and secured to each corner of tank stand with a doublestrand of 4mm diameter galvanised wire embedded into concrete. (Note: Tank to be filled with water before Practical Completion).	No	4
36	Hole through top of tank lid for 100mm diameter pipe	No	4
	Carried Forward		R
Section No. 2 Bill No. 15 EXTERNAL WORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>TAPS, VALVES, ETC..</u>			
37	Approved 15mm standard brass hose bibtap with wingnut, lining and 15mm hose union, manufactured in accordance with SANS 226:2009 Type 2 (BS 1010).	No	4
<u>LOCKS</u>			
<u>The following locks are to be suitable for master and grand master key operation</u>			
<u>"Dorma" or similar approved</u>			
38	50mm Brass padlock with 28mm Stainless Steel	No	4
<u>MISCELLANEOUS.</u>			
<u>Supply and fit complete to manufacturer's standards the following to downpipes and tanks to prevent blocking and intrusion of mosquitoes and pests to tanks.</u>			
39	Leaf eater rain heads	No	4
40	Screen filter	No	4
41	First flush diverters	No	4
<u>APRONS</u>			
Carried Forward			R
Section No. 2 Bill No. 15 EXTERNAL WORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Compaction of surfaces</u>			
42	Compaction of ground surface under ramps, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	132
<u>Prescribed density tests on filling</u>			
43	"Modified AASHTO Density" test	No	5
<u>15MPa/19mm unreinforced concrete</u>			
44	Aprons laid in panels	m3	20
45	Extra over concrete aprons for thickening size 150mm deep, 200mm top and tapering to 100mm at bottom including all excavation to 100mm, backfilling, etc.	m	110
<u>Finishing top surfaces of concrete smooth with a wood trowel</u>			
46	Aprons to falls	m2	132
<u>Rough formwork to sides</u>			
47	Edges, risers, etc. not exceeding 300mm high or wide	m	110
<u>Fabric reinforcement:</u>			
48	REF. 193 fabric reinforcement in concrete aprons, slabs, etc.	m2	132
Carried Forward			R
Section No. 2 Bill No. 15 EXTERNAL WORKS			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

		Brought Forward			R
	<u>RAMPS</u>				
	<u>Excavation in earth or compacted platforms not exceeding 2m deep</u>				
49	Trenches	m3	18		
	<u>Risk of collapse of excavations</u>				
50	Sides of trench and hole excavations not exceeding 1,5m deep	m2	36		
	<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>				
51	Backfilling to trenches, holes, etc	m3	23		
	<u>Compaction of surfaces</u>				
52	Compaction of ground surface under ramps, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	44		
	<u>Prescribed density tests on filling</u>				
53	"Modified AASHTO Density" test	No	5		
	<u>Soil poisoning and insecticide</u>				
54	Under ramps, etc including forming and poisoning shallow furrows against foundation walls, etc, filling in furrows and ramming	m2	44		
		Carried Forward			R
	Section No. 2				
	Bill No. 15				
	EXTERNAL WORKS				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

		Brought Forward			R
55	To bottoms and sides of trenches, etc	m2	36		
	<u>15MPa/19mm unreinforced concrete</u>				
56	Ramps laid in panels	m3	14		
57	Extra over concrete ramps for thickening size 150mm deep, 200mm top and tapering to 100mm at bottom including all excavation to 100mm, backfilling, etc.	m	110		
	<u>Finishing top surfaces of concrete smooth with a wood trowel</u>				
58	Ramps to falls	m2	44		
	<u>Brickwork of NFX bricks in class I mortar</u>				
59	One brick walls in foundations	m2	40		
	<u>Brickwork reinforcement</u>				
60	150mm Wide reinforcement built in horizontally in foundations	m	142		
	<u>"Corobrik Firelight Satin" face bricks pointed with recessed horizontal and vertical joints</u>				
61	Extra over brickwork for face brickwork in foundations	m2	40		
	<u>Brick-on-edge header course copings, sills, etc of "Corobrik Firelight Satin" face bricks pointed with recessed joints on all exposed faces</u>				
62	Coping on top of one brick wall	m	50		
		Carried Forward			R
	Section No. 2				
	Bill No. 15				
	EXTERNAL WORKS				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

		Brought Forward			R
<u>STORMWATER DRAINAGE</u>					
<u>CONCRETE</u>					
<u>Mass concrete with a coarse aggregate of 9mm and a minimum compressive strength of 15MPa at 28 days</u>					
63	V- shaped channel 900mm wide x 100mm thick with rounded salient edges and finished on exposed surfaces with 2:1 cement mortar laid to falls in panels not exceeding 1,8m long with 12mm bitumen impregnated softboard movement joints with exposed edges raked out for a depth of 10mm and filled with bituminous compound including all necessary excavations and formwork	m	120		
64	Extra for fair open end	No	5		
65	Extra for fair stopped end	No	3		
66	Extra for angle intersection	No	2		
<u>Movement joints</u>					
67	Movement joint not exceeding 300mm high formed of 12mm bitumen impregnated softboard placed vertical in position between concrete stormwater channel and brick walls or concrete aprons, etc including raking out top section 10mm deep and filling with bituminous compound	m	102		
Carried Forward to Summary of Section No. 2					
Section No. 2					R
Bill No. 15					
EXTERNAL WORKS					

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Bill No	SECTION SUMMARY - BUILDING WORKS	Page No	Amount
1	ALTERATIONS	28	
2	EARTHWORKS	31	
3	CONCRETE, FORMWORK AND REINFORCEMENT	34	
4	PRECAST CONCRETE	35	
5	MASONRY	38	
6	WATERPROOFING	39	
7	ROOF COVERING	40	
8	CARPENTRY AND JOINERY	42	
9	IRONMONGERY	44	
10	METALWORK	47	
11	PLASTERING	48	
12	PLUMBING AND DRAINAGE	51	
13	GLAZING	52	
14	PAINTWORK	54	
15	EXTERNAL WORKS	64	
Carried to Final Summary			R
Section No. 2			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION NO.3</u>			
	<u>OCCUPATIONAL HEALTH AND SAFETY</u>			
	<u>BILL NO.1</u>			
	<u>COVID 19 SPECIFICATION</u>			
	<u>General</u>			
1	Review of OHS Plan for each assignment. Rate to include for risk assessment specific to COVID-19 pandemic and other adjustments to ensure compliance for the assignment (Once off for the duration of contract)	Item		
2	Principal Contractor's Fixed Cost obligation in respect of the OHS Act and Construction Regulations signage - COVID-19 related (once off for the duration of contract)	Item		
3	Non-contact thermal scanner	No	2	
4	Kimberly Clark Metal Blue Free Standing, Portable Paper Towel Dispenser, 570mm x 790mm x 160mm	No	2	
5	Additional 240 litre wheeled bins 725mm(L) x 58mm(W) x 1,075mm(H)	No	5	
6	Provision for isolation area (screened and ventilated with appropriate signage) (H)			SUM
7	Disinfection of isolation area			SUM
8	Biohazard waste box set - 30 litre (5kg)	No	1	
	Carried Forward			R
	Section No. 3			
	Bill No. 1			
	COVID-19 SPECIFICATION			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward			R
9	Removal of biohazard waste to nearest clinic			SUM
10	Transport to nearest clinic			SUM
11	Disinfection of transport	No	1	
	<u>DISINFECTION OF AMENITIES</u>			
12	Surface cleaner (5 litre containers)	No	20	
13	Spray bottles (500 ml) with label sticker	No	32	
14	Essential Wiper Roll - 1 Ply - White - 205mm x 1,500m	No	10	
15	30 micron disposable garbage bags (200 bags / pack)	No	10	
	<u>DISINFECTION OF TOOLS & EQUIPMENT</u>			
16	Surface cleaner (5 litre containers)		Item	
17	30 micron disposable garbage bags (200 bags / pack)		Item	
	<u>PPE</u>			
18	"Suitable re-usable cloth facemask (3 per person per month) (Visitors to supply own masks)"		Item	
19	0.4mm PET curved visor adjustable 2-piece face shield (10% of labour force allowance)		Item	
20	Face shield and surgical masks (N95, FFP2) for first aider, appointed C-19 Control Officer, screening person, cleaner		Item	
	Carried Forward			R
	Section No. 3			
	Bill No. 1			
	COVID-19 SPECIFICATION			

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

	Brought Forward		R	
21	Latex re-usable cleaner gloves (4 pairs / user/ month) - 10 person allowance	Item		
22	Disposable aprons (100 aprons / pack) - 1 pack allowance / month	Item		
23	Non-contact thermal scanner (breakage allowance)	Item		
24	Hand sanitiser 70% alcohol-based (5l containers)	Item		
25	Spray bottles (500 ml) with label sticker	Item		
26	Essential Wiper Roll - 1 Ply - White - 205mm x 1,500m (for personnel use)	Item		
27	Monthly lump sum allowance for additional remuneration for COVID-19 compliance officer and/or assistant	Item		
28	Lump sum per month for administration & training costs and stationery expenses	Item		
Carried Forward to Summary of Section No. 3			R	
Section No. 3				
Bill No. 1				
COVID-19 SPECIFICATION				

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Item No		Quantity	Rate	Amount
	<u>SECTION NO.3</u>			
	<u>OCCUPATIONAL HEALTH AND SAFETY</u>			
	<u>BILL NO.2</u>			
	<u>OHS</u>			
1	Preparation of the Contractors site specific Health and Safety Plan (Refer to Item 1.3 of H & S Specification).	Item		
	<u>Provision of Personal Protective Equipment (PPE) (Refer to item 2.3.20 of H & S Specification):</u>			
2	(a) Reflective vests	No	20	
3	(b) Hard hat	No	20	
4	(c) Protective foot wear	No	20	
5	(d) Earplugs	No	100	
6	(e) Dust masks	No	100	
7	(f) Gloves	No	20	
8	Provision of a part time Construction Health and Safety Officer (Refer to item 2.3.8 of H & S Specification).	No	4	
	Carried Forward			
	Section No. 3 Bill No. 2 OHS		R	

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

Brought Forward			R
<u>Cost of medical certificates and medical surveillance (Refer to Item 2.6.1 of H & S Specification):</u>			
9	(a) Initial (baseline) medical examinations	Item	
10	(b) Exit examinations	Item	
11	(c) Contractors charge to allow for handling costs and profit in respect of items 9 and 10	Item	
12	Provision of First Aid Boxes to GSR requirements (Refer to Item 2.3.17 of H&S Specification).	No	1
<u>General items:</u>			
13	Provision for Signage (Refer to Item 2.3.21 of H& S Specification)	Item	
14	OHS Relevant Training (hiv/aids, SHE Rep, Scaffold erector & inspector, First Aider etc.) Refer to Item 2.3.10 H&S Specification	Item	
15	Submission of a Health and Safety File (Refer to Item 2.7 of H&S Specification).	Item	
16	Access Scaffolding (Kwikstage) (Refer to Item 2.4.1) of H&S Specification)	Item	
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Bill No. 2			
OHS			

Bill No	<u>SECTION SUMMARY - OCCUPATIONAL HEALTH AND SAFETY</u>		Page No			Amount
1	COVID-19 SPECIFICATION		68			
2	OHS		70			
Section No. 3		Carried to Final Summary			R	

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**

[illegible]

**SILIMELA SENIOR PRIMARY SCHOOL
CONSTRUCTION OF NEW ABLUTION BLOCKS**