


DOOR SCHEDULE

NOTE: Dimensions shown are actual brickwork opening sizes.
All dimensions to be checked and verified on site prior to manufacture.



Quantity: 02
Position: As indicated on plan.
Contractor to check plans for LH/RH openings.

D01

DESCRIPTION
40mm thick horizontal grooved heavy duty hardwood door with exposed edges, frame size 900 x 2 100mm high, with leaf size 813 x 2 032mm high. 70x90mm Rebated meranti timber door frame.



FRAME
70x90mm Rebated meranti timber door frame.

FINISH
All blemishes in timber to be filled and sanded down and prepared for painting.

Finish to be selected and approved.

IRONMONGERY
Refer to Ironmongery Schedule.

GLAZING
Not Applicable

OTHER NOTES				APPROVAL			
				DEPARTMENT	NAME	DATE	SIGNATURE
				SDL			
				DBI			
				DBSA			
<div><div></div><div><p>The contractor is to keep a full set of drawings on site, contractor is responsible for the correct setting out of the building on site with reference to boundaries and building lines, contractor to verify all levels and dimensions on site and check same against architects and engineers drawings before commencing work. Figured dimensions to be used in preference to scaled dimensions, large scale details to be used where available, errors, discrepancies or omissions are to be reported to the architect immediately for clarification before work is undertaken.</p><p>These drawings are to be read in conjunction with structural engineers, civil engineers, mechanical engineer's or plumbing consultant's drawings were specified.</p><p>All work and material used to comply with SABS standards and NATIONAL BUILDING REGULATIONS ACT 103 of 1977 and amendments thereto as well as the by-laws of the relevant local authority.</p><p>All new construction HEALTH AND SAFETY Regulations to be strictly complied with.</p></div></div>				PROJECT NAME		ISSUED FOR	
				FREESTATE MEGA SCHOOLS: DOOR SCHEDULES		FOR TENDER	PROJECT NO.
							175
						DRAWING NAME	DRAWING NO.
				DOOR SCHEDULE			35 SEC-W.DS.01
						DATE:	2022/06/28
						DRAWN BY:	LGM
						CHECKED BY:	FM