


GATE SCHEDULE



Quantity: 02
Position: As indicated on plan.
Contractor to check plans for LH/RH openings.

G01


DESCRIPTION
Shutterway Stylish Security gate, to fit door opening 900x2100mm, and fixed to inside of door threshold all as per manufacturers recommendation and specifications.

FRAME
31.7x31.7mm square hollow steel section, with 40mm flat bar louvres, all as per manufacturers specification,

FINISH
Steel to be powder-coated, colour: "matt charcoal" all as per manufacturers specifications.

LOUVRES
40mm flat bar louvres welded at 48° at max 116mm spacing, factory fitted as per manufacturers specifications.

IRONMONGERY
Factory fitted double throw dead-lock on cover plate, as per manufacturers specifications.



Quantity: 01
Position: As indicated on plan.
Contractor to check plans for LH/RH openings.

G04

DESCRIPTION
Shutterway Stylish Security gate, to fit door opening 1 600x2 100mm, and fixed to inside of door threshold all as per manufacturers recommendation and specifications.


FRAME
31.7x31.7mm square hollow steel section, with 40mm flat bar louvres, all as per manufacturers specification,





FINISH
Steel to be powder-coated, colour: "matt charcoal" all as per manufacturers specifications.

LOUVRES
40mm flat bar louvres welded at 48° at max 116mm spacing, factory fitted as per manufacturers specifications.

IRONMONGERY
Factory fitted double throw dead-lock on cover plate, as per manufacturers specifications.

GATE SPECIFICATION



OTHER NOTES				APPROVAL			
				DEPARTMENT	NAME	DATE	SIGNATURE
				SDL			
				DBI			
				DBSA			
<div><div><div>education</div><div>Department of Education FREE STATE PROVINCE</div></div><div><div>DBSA</div><div>DEVELOPMENT BANK OF SOUTH AFRICA</div></div><div><div>DBI</div><div>CONSULTING</div></div><div><div>SONGO DESIGN LAB</div><div>ARCHITECTURE + PROJECT MANAGEMENT</div><div>48 Hillcrest Dr, Blue Bend, East London, 5201</div><div>043 748 1800</div></div><div><div>The contractor is to keep a full set of drawings on site, contractor is responsible for the correct setting out of the building on site with reference to boundaries and building lines, contractor to verify all levels and dimensions on site and check same against architects and engineers drawings before commencing work. Figured dimensions to be used in preference to scaled dimensions, large scale details to be used where available, errors, discrepancies or omissions are to be reported to the architect immediately for clarification before work is undertaken.</div><div>These drawings are to be read in conjunction with structural engineers, civil engineers, mechanical engineer's or plumbing consultant's drawings were specified.</div><div>All work and material used to comply with SABS standards and NATIONAL BUILDING REGULATIONS ACT 103 of 1977 and amendments thereto as well as the by-laws of the relevant local authority.</div><div>All new construction HEALTH AND SAFETY Regulations to be strictly complied with.</div></div></div>				PROJECT NAME			
				FREESTATE MEGA SCHOOLS: GATE SCHEDULES			
				ISSUED FOR			
				FOR TENDER			
				DRAWING NAME			
				GATE SCHEDULE			
				PROJECT INFORMATION			
				PROJECT NO.	175		
				DRAWING NO.	26 MED-L..GS.01		
				DATE:	2022/10/16		
				DRAWN BY:	LGM		
				CHECKED BY:	FM		