



- NOTE:
1. CONCRETE TO BE CAST IN 14m LENGTHS WITH EXPANSION JOINTS, AND SAW CUT JOINTS (S.J.) TO BE PROVIDED EVERY 2m.
 2. EXPANSION JOINT TO COMPRISE OF 12mm SOFTBOARD TO FULL DEPTH OF CONCRETE.
 3. TOP 10mm OF SOFTBOARD TO BE RAKED OUT AND FILLED WITH APPROVED UV RESISTANT POLYSULPHIDE SEALANT.
 4. TOP SURFACE TO HAVE WOOD FLOAT FINISH.

DBSA

DEVELOPMENT BANK OF SOUTHERN AFRICA

Building Africa's Prosperity

IMPUMELELO

consulting engineers

PLAN DESCRIPTION

DWG. NO.

SHEET NO.

CONTINUED FROM

CONTINUED ON

CROSS SECTIONS

TYPICAL CROSS SECTION

SURVEY LAYOUT

REDUCED PLAN USE SCALE BELOW

0 10 20 30 40 50

50mm ON ORIGINAL PLAN

REV 0A

16/09/2022

ISSUED FOR TENDER

REVISION

DATE

DESCRIPTION

NOTE:

No construction work to commence until land and servitude acquisitions have been completed

Acquisitions completed

DATE

Engineer

UNDERGROUND SERVICES CHECKED

SERVICE

DATE

SIGNATURE

S.W.DRAINS

SEWERS

WATER MAINS

G.P.O.CABLES

ELECTRIC CABLES

S.A.R. CABLES

E.S.C. CABLES

OIL PIPE LINE

Contract No.

Project Title

DUMEHLEZI HIGH SCHOOL

Project Description :

ASBESTOS REPLACEMENT

Scales

Reference

Designed : M.Cele

Date : 16-09-2022

Checked : N.Ndlovu

Drawn by : Q.Mahaye

Drawing Description :

TYPICAL DETAILS

Sheet

of