

NOMYACA HIGH-SCHOOL – SCOPE OF WORK

BLOCK A

- Remove asbestos roof sheeting including purlins, trusses and make good. Install new sheet metal roof sheeting with colour coat applied finish, concealed fixing clips to comply with SANS1200-hb. purlin spacing according to manufacturer's specification, all to architect's approval. colour to match existing on site sheeting. Ridge capping - standard factory manufactured ridges and flashings, finish to match roof covering.
- New timber roof trusses to be designed and manufactured by an approved licenced timber truss specialist. To include timber purlins and all necessary bracing etc. All design information to be issued to engineer for approval prior to manufacture of trusses. A certificate of compliance to be issued on completion of work. Note new trusses to be fixed back to existing trusses.
- Existing standard pressed metal door frame. Make good to frame as required. Broken hinges to frame to be removed and provide new (Also provide new where hinges are missing) welded to the frames in correct positions. (9 Standard doors)
- Remove existing floor finish as required and make good to screed. Prepare floor to receive new tiles to standard specifications strict accordance with manufacturers specification etc. Colour to be confirmed by architect. [Block A: 190 sqm]
- Install new light fittings. Install new 13W LED bulkhead light fittings and replace wiring and conduit where necessary.
- Install new blank covers and warning labels. Install new circuit breaker blank covers and warning labels for DB and issue Certificate of compliance.
- Install new Level IV lightning protection installation according to SANS 10313, Issue earthing test certificate achieving 10 ohms or less.
- Reseal all joints in walkway and apron slabs. Reseal with polysulphide sealant. Where there is no joint present but walkway or apron slab has cracked in a joint position, repair as follows:
 - Removal of cracked and delaminated concrete
 - Apply wet to dry epoxy mortar
 - Application of repair mortar or micro-concrete to replace damaged concrete
 - Saw-cut joint to be done and sealed with polysulphide sealant.

JOHANNESBURG	CAPE TOWN	BLOEMFONTEIN	NORTH WEST	EASTERN CAPE	DURBAN	LIMPOPO
HEAD OFFICE						
32 Fricker Road	1 Century City Drive	Reitz Park Complex	186 Klopper Street	22 Alexandra Road	Royal Palm Hotel	Consillium Building
Illovo	Century City	74-80 President	Rustenburg	King William's Town	3rd Floor Suite 3C	Ground Floor
Sandton	Cape Town	Reitz Avenue	North West	Eastern Cape	6 Palm Boulevard	18 General Beyers Street

BLOCK B

- Remove asbestos roof sheeting including purlins, trusses and make good. Install new sheet metal roof sheeting with colour coat applied finish, concealed fixing clips to comply with SANS1200-hb. purlin spacing according to manufacturer's specification, all to architect's approval. colour to match existing on site sheeting. Ridge capping - standard factory manufactured ridges and flashings, finish to match roof covering. [Block B: 233,32 sqm].
- New timber roof trusses to be designed and manufactured by an approved licenced timber truss specialist. To include timber purlins and all necessary bracing etc. All design information to be issued to engineer for approval prior to manufacture of trusses. A certificate of compliance to be issued on completion of work. Note new trusses to be fixed back to existing trusses.
- Install new rainwater fascia board, gutter and downpipe. [PVC gutter and downpipes, fibre cement barge board to KZN DoE standard specification.
- Existing standard pressed metal door frame. Make good to frame as required. Broken hinges to frame to be removed and provide new (Also provide new where hinges are missing) welded to the frames in correct positions. (4 Standard doors)
- Remove existing floor finish as required and make good to screed. Prepare floor to receive new tiles to standard specifications strict accordance with manufacturers specification etc. Colour to be confirmed by architect. [Block B: 233,32 sqm]
- x13 broken 950x1440mm steel windowpanes are to be removed, replace and make good. New window to match existing.
- Remove all existing chalk boards and replace with new chalkboard to standard specifications. [x14 Chalkboard. All classrooms]
- Install new light fittings. Install new 13W LED bulkhead light fittings and replace wiring and conduit where necessary.
- Install new blank covers and warning labels. Install new circuit breaker blank covers and warning labels for DB and issue Certificate of compliance.
- Install new Level IV lightning protection installation according to SANS 10313, Issue earthing test certificate achieving 10 ohms or less.
- Reseal all joints in walkway and apron slabs. Reseal with polysulphide sealant. Where there is no joint present but walkway or apron slab has cracked in a joint position, repair as follows:
 - Removal of cracked and delaminated concrete

JOHANNESBURG	CAPE TOWN	BLOEMFONTEIN	NORTH WEST	EASTERN CAPE	DURBAN	LIMPOPO
HEAD OFFICE						
32 Fricker Road	1 Century City Drive	Reitz Park Complex	186 Kloppe Street	22 Alexandra Road	Royal Palm Hotel	Consillium Building
Illovo	Century City	74-80 President	Rustenburg	King William's Town	3rd Floor Suite 3C	Ground Floor
Sandton	Cape Town	Reitz Avenue	North West	Eastern Cape	6 Palm Boulevard	18 General Beyers Street

- Apply wet to dry epoxy mortar
- Application of repair mortar or micro-concrete to replace damaged concrete
- Saw-cut joint to be done and sealed with polysulphide sealant.

BLOCK C

- Remove asbestos roof sheeting including purlins, trusses and make good. Install new sheet metal roof sheeting with colour coat applied finish, concealed fixing clips to comply with SANS1200-hb. purlin spacing according to manufacturer's specification, all to architect's approval. colour to match existing on-site sheeting. Ridge capping - standard factory manufactured ridges and flashings, finish to match roof covering. [Block C: 233,32 sqm].
- New timber roof trusses to be designed and manufactured by an approved licenced timber truss specialist. To include timber purlins and all necessary bracing etc. All design information to be issued to engineer for approval prior to manufacture of trusses. A certificate of compliance to be issued on completion of work. Note new trusses to be fixed back to existing trusses.
- Install new rainwater fascia board, gutter and downpipe. [PVC gutter and downpipes, fibre cement barge board to KZN DoE standard specification.
- Existing standard pressed metal door frame. Make good to frame as required. Broken hinges to frame to be removed and provide new (Also provide new where hinges are missing) welded to the frames in correct positions. (4 Standard doors)
- Remove existing floor finish as required and make good to screed. Prepare floor to receive new tiles to standard specifications strict accordance with manufacturers specification etc. Colour to be confirmed by architect. [Block C: 233,32 sqm]
- x14 broken 950x1440mm steel windowpanes are to be removed, replace and make good. New window to match existing.
- Install new light fittings. Install new 13W LED bulkhead light fittings and replace wiring and conduit where necessary.
- Install new blank covers and warning labels. Install new circuit breaker blank covers and warning labels for DB and issue Certificate of compliance.
- Install new Level IV lightning protection installation according to SANS 10313, Issue earthing test certificate achieving 10 ohms or less.

JOHANNESBURG	CAPE TOWN	BLOEMFONTEIN	NORTH WEST	EASTERN CAPE	DURBAN	LIMPOPO
HEAD OFFICE						
32 Fricker Road	1 Century City Drive	Reitz Park Complex	186 Kloppe Street	22 Alexandra Road	Royal Palm Hotel	Consillium Building
Illovo	Century City	74-80 President	Rustenburg	King William's Town	3rd Floor Suite 3C	Ground Floor
Sandton	Cape Town	Reitz Avenue	North West	Eastern Cape	6 Palm Boulevard	18 General Beyers Street

- Reseal all joints in walkway and apron slabs. Reseal with polysulphide sealant. Where there is no joint present but walkway or apron slab has cracked in a joint position, repair as follows:
 - Removal of cracked and delaminated concrete
 - Apply wet to dry epoxy mortar
 - Application of repair mortar or micro-concrete to replace damaged concrete
 - Saw-cut joint to be done and sealed with polysulphide sealant.

BLOCK D

- Remove asbestos roof sheeting including purlins, trusses and make good. Install new sheet metal roof sheeting with colour coat applied finish, concealed fixing clips to comply with SANS1200-hb. purlin spacing according to manufacturer's specification, all to architect's approval. colour to match existing on-site sheeting. Ridge capping - standard factory manufactured ridges and flashings, finish to match roof covering. [Block D: 233,32 sqm].
- New timber roof trusses to be designed and manufactured by an approved licenced timber truss specialist. To include timber purlins and all necessary bracing etc. All design information to be issued to engineer for approval prior to manufacture of trusses. A certificate of compliance to be issued on completion of work. Note new trusses to be fixed back to existing trusses.
- New industrial grade reinforced aluminium foil insulation double sided reflective foil laminate supported between purlins by 1.6mm dia. double galvanised straining wires installed following manufacturers specification and requirements.
- Install new rainwater fascia board, gutter and downpipe. [PVC gutter and downpipes, fibre cement barge board to KZN DoE standard specification.
- Existing standard pressed metal door frame. Make good to frame as required. Broken hinges to frame to be removed and provide new (Also provide new where hinges are missing) welded to the frames in correct positions. (4 Standard doors)
- Remove existing floor finish as required and make good to screed. Prepare floor to receive new tiles to standard specifications strict accordance with manufacturers specification etc. Colour to be confirmed by architect. [Block D: 233,32 sqm]
- x9 broken 950x1440mm steel windowpanes are to be removed, replace and make good. New window to match existing.
- Install new light fittings. Install new 13W LED bulkhead light fittings and replace wiring and conduit where necessary.

JOHANNESBURG	CAPE TOWN	BLOEMFONTEIN	NORTH WEST	EASTERN CAPE	DURBAN	LIMPOPO
HEAD OFFICE						
32 Fricker Road	1 Century City Drive	Reitz Park Complex	186 Klopper Street	22 Alexandra Road	Royal Palm Hotel	Consillium Building
Illovo	Century City	74-80 President	Rustenburg	King William's Town	3rd Floor Suite 3C	Ground Floor
Sandton	Cape Town	Reitz Avenue	North West	Eastern Cape	6 Palm Boulevard	18 General Beyers Street

- Install new blank covers and warning labels. Install new circuit breaker blank covers and warning labels for DB and issue Certificate of compliance.
- Install new Level IV lightning protection installation according to SANS 10313, Issue earthing test certificate achieving 10 ohms or less.
- Reseal all joints in walkway and apron slabs. Reseal with polysulphide sealant. Where there is no joint present but walkway or apron slab has cracked in a joint position, repair as follows:
 - Removal of cracked and delaminated concrete
 - Apply wet to dry epoxy mortar
 - Application of repair mortar or micro-concrete to replace damaged concrete
 - Saw-cut joint to be done and sealed with polysulphide sealant.

BLOCK E

- Remove asbestos roof sheeting including purlins, trusses and make good. Install new sheet metal roof sheeting with colour coat applied finish, concealed fixing clips to comply with SANS1200-hb. purlin spacing according to manufacturer's specification, all to architect's approval. colour to match existing on-site sheeting. Ridge capping - standard factory manufactured ridges and flashings, finish to match roof covering. [Block E: 233 sqm].
- New timber roof trusses to be designed and manufactured by an approved licenced timber truss specialist. To include timber purlins and all necessary bracing etc. All design information to be issued to engineer for approval prior to manufacture of trusses. A certificate of compliance to be issued on completion of work. Note new trusses to be fixed back to existing trusses.
- New industrial grade reinforced aluminium foil insulation double sided reflective foil laminate supported between purlins by 1.6mm dia. double galvanised straining wires installed following manufacturers specification and requirements.
- Install new rainwater fascia board, gutter and downpipe. [PVC gutter and downpipes, fibre cement barge board to KZN DoE standard specification.
- Existing standard pressed metal door frame. Make good to frame as required. Broken hinges to frame to be removed and provide new (Also provide new where hinges are missing) welded to the frames in correct positions. (4 Standard doors)
- Remove existing floor finish as required and make good to screed. Prepare floor to receive new tiles to standard specifications strict accordance with manufacturers specification etc. Colour to be confirmed by architect. [Block E: 233 sqm]

JOHANNESBURG	CAPE TOWN	BLOEMFONTEIN	NORTH WEST	EASTERN CAPE	DURBAN	LIMPOPO
HEAD OFFICE						
32 Fricker Road	1 Century City Drive	Reitz Park Complex	186 Kloppe Street	22 Alexandra Road	Royal Palm Hotel	Consillium Building
Illovo	Century City	74-80 President	Rustenburg	King William's Town	3rd Floor Suite 3C	Ground Floor
Sandton	Cape Town	Reitz Avenue	North West	Eastern Cape	6 Palm Boulevard	18 General Beyers Street

- Provide adequate storage facility. Build new Storage and Kitchen facilities to comply with standards. Building materials to be used during construction must be those that are approved by the SANS.
- Install new light fittings. Install new 13W LED bulkhead light fittings and replace wiring and conduit where necessary.
- Install new blank covers and warning labels. Install new circuit breaker blank covers and warning labels for DB and issue Certificate of compliance.
- Install new Level IV lightning protection installation according to SANS 10313, Issue earthing test certificate achieving 10 ohms or less.
- Reseal all joints in walkway and apron slabs. Reseal with polysulphide sealant. Where there is no joint present, but walkway or apron slab has cracked in a joint position, repair as follows:
 - Removal of cracked and delaminated concrete
 - Apply wet to dry epoxy mortar
 - Application of repair mortar or micro-concrete to replace damaged concrete
 - Saw-cut joint to be done and sealed with polysulphide sealant.

NOTE:

Existing ablution block to be demolished due to extreme deterioration. Build new structure as per design documentation provided.

JOHANNESBURG	CAPE TOWN	BLOEMFONTEIN	NORTH WEST	EASTERN CAPE	DURBAN	LIMPOPO
HEAD OFFICE						
32 Fricker Road	1 Century City Drive	Reitz Park Complex	186 Klopper Street	22 Alexandra Road	Royal Palm Hotel	Consillium Building
Illovo	Century City	74-80 President	Rustenburg	King William's Town	3rd Floor Suite 3C	Ground Floor
Sandton	Cape Town	Reitz Avenue	North West	Eastern Cape	6 Palm Boulevard	18 General Beyers Street

PROJECT/PROPOSAL NAME	KZN DOE INFRASTRUCTURE DEVELOPMENT AND MAINTANANCE PROGRAMME	PROJECT No	5152
TITLE DOCUMENT	PROJECT ASSESSMENT REPORT: NOMYACA HIGH SCHOOL		
ELECTRONIC LOCATION			

	Approved by	Reviewed by	Prepared by
ORIGINAL	TITLE: COO NAME:	TITLE: DIRECTOR RISK NAME:	TITLE: PROJECT MANAGER NAME:
DATE	SIGNATURE	SIGNATURE	SIGNATURE

This report, and information or advice, which it contains, is provided by IKG solely for internal use and reliance by its Client in performance of IKG duties and liabilities under its contract with the Client. Any advice, opinions, or recommendations within this report should be read and relied upon only in the context of the report. The advice and opinions in this report are based upon the information made available to IKG at the date of this report and on current SA standards, codes, technology and construction practices as at the date of this report. Following final delivery of this report to the Client, IKG will have no further obligations or duty to advise the Client on any matters, including development affecting the information or advice provided in this report. This report has been prepared by IKG in their professional capacity as Professional Consultants. The contents of the report do not, in any way, purport to include any manner of legal advice or opinion. This report is prepared in accordance with the terms and conditions of the IKG contract with the Client. Regard should be had to those terms and conditions when considering and/or placing any reliance on this report. Should the Client wish to release this report to a Third Party for that party's reliance, IKG may, at its discretion, agree to such release provided that:

- IKG written agreement is obtained prior to such release, and
- By release of the report to the Third Party, that Third Party does not acquire any rights, contractual or otherwise, whatsoever against IKG and IKG, accordingly, assume no duties, liabilities or obligations to that Third Party, and
- IKG accepts no responsibility for any loss or damage incurred by the Client or for any conflict of IKG interests arising out of the Client's release of this report to the Third Party.

IKG (Pty) Ltd

Website: www.indigo-group.co.za

Postal Address 32 Fricker Road, Illovo, Sandton

Physical Address: 32 Fricker Rd, Illovo, Sandton

Contact Person

Email Address: tenders@indigo-group.co.za

Telephone No 086 111 2221

Fax No 086 690 6963

JOHANNESBURG	CAPE TOWN	BLOEMFONTEIN	NORTH WEST	EASTERN CAPE	DURBAN	LIMPOPO
HEAD OFFICE						
32 Fricker Road	1 Century City Drive	Reitz Park Complex	186 Kloppe Street	22 Alexandra Road	Royal Palm Hotel	Consillium Building
Illovo	Century City	74-80 President	Rustenburg	King William's Town	3rd Floor Suite 3C	Ground Floor
Sandton	Cape Town	Reitz Avenue	North West	Eastern Cape	6 Palm Boulevard	18 General Beyers Street